

**Haines Public Safety Building
Level 1 Submittal
Haines, Alaska**

**Construction Cost Estimate
June 18, 2013**



1225 E. International Airport Road, Suite 205
Anchorage, Alaska 99518
907.561.0790

Prepared for:
McCool Carlson Green Architects
421 West 1st Avenue, Suite 300
Anchorage, Alaska 99501
907.563.8474

Documents
Concept Sketches

Area Calculation

Floor 1	19,500 SF
Floor 2	- SF
Total	19,500 SF

Notes and Assumptions

- 1 Based on 2014 procurement/2014 construction.
- 2 Labor rates based on Davis Bacon, 60 hours/week.
- 3 Weather, logistics and construction time window has been considered, assume a spring NTP.
- 4 Assumes open competitive bid procurement.
- 5 Building Permits are not included in the estimate.
- 6 Sufficient Water Pressure will be Present for Fire Flow.

Excluded

- 1 Furniture Fixtures and Equipment including, desks, carrels, chairs, office system furniture.
- 2 Design, Construction Administration, Geological Investigation.
- 3 No hazardous cleanup of site if contaminants are present.

Item	Qty	Unit	Unit Cost	Line Cost	Total Cost	Unit Cost
Summary (Level 2)						
A SUBSTRUCTURE	19,500	GSF	\$30.41		\$592,915	
B SHELL	19,500	GSF	\$72.23		\$1,408,440	
C INTERIORS	19,500	GSF	\$48.64		\$948,415	
D SERVICES	19,500	SF	\$103.93		\$2,026,715	
E EQUIPMENT & FURNISHINGS	19,500	GSF	\$7.19		\$140,275	
F SPECIAL CONSTRUCTION AND DEMOLITION	-	GSF	\$0.00		\$0	
G SITEWORK	19,500	GSF	\$22.27		\$434,308	
Z MARKUPS	19,500	GSF	\$145.28		\$2,832,917	
Total Estimated Cost	19,500	GSF	\$429.95		\$8,383,984	

Item	Qty	Unit	Unit Cost	Line Cost	Total Cost	Unit Cost
Detail (Level 3)						
A SUBSTRUCTURE	19,500	GSF			\$592,915	\$30.41
A10 Foundations	19,500	GSF			\$592,915	\$30.41
Foundation Walls, 8" W/ 4" Rigid Insulation & D.Proofing	698	LF	\$163.16	\$113,889		
Pile Caps	67	EA	\$1,850.86	\$124,008		
Grade Beams	1,950	LF	\$125.44	\$244,599		
Slab On Grade 4"	12,645	SF	\$8.73	\$110,419		
Slab On Grade 6"	6,855	SF	\$12.41	\$85,095		
A20 Basement	-	NONE			\$0	\$0.00
B SHELL	19,500	GSF			\$1,408,440	\$72.23
B10 Superstructure	19,500	SF			\$439,341	\$22.53
Roof Construction						
Steel Deck On Steel Frame	19,500	SF	\$22.53	\$439,341		
B20 Exterior Closure	11,168	SF			\$589,258	\$52.76
Exterior Walls, Metal Framing, Rigid Insulation 2", Batts, Air Barrier, Vapor Barrier and GWB	11,168	SF	\$16.88	\$188,560		
Siding	11,168	SF	\$20.00	\$223,360		
Exterior Doors, IHM	13	LV	\$3,017.62	\$39,229		
OH Doors	4	EA	\$12,000.00	\$48,000		
Aluminum Entrances	2	LV	\$1,750.00	\$3,500		
Alum Windows	1,125	SF	\$75.00	\$84,375		
Exterior Accessories	11,168	SF	\$0.20	\$2,234		
B30 Roofing	19,500	SF			\$379,841	\$19.48
EPDM Roofing System R60	19,500	SF	\$19.48	\$379,841		

Item	Qty	Unit	Unit Cost	Line Cost	Total Cost	Unit Cost
Detail (Level 3)						
C INTERIORS	19,500	GSF			\$948,415	\$48.64
C10 Interior Construction	19,500	SF			\$440,231	\$22.58
Partitions/Soffits	27,264	SF	\$7.32	\$199,681		
Relites	140	SF	\$35.00	\$4,900		
Interior Storefront Glazing	140	SF	\$65.00	\$9,100		
Interior Doors	66	LV	\$1,405.00	\$92,730		
Sliding Doors	3	EA	\$4,500.00	\$13,500		
Interior Fittings	19,500	SF	\$3.00	\$58,500		
Cabinet, Base With Counters (Solid Surface)	42	LF	\$420.00	\$17,640		
Cabinets, Uppers	22	LF	\$155.00	\$3,410		
Toilet Accessories	7	SETS	\$3,000.00	\$21,000		
Toilet Partitions	9	EA	\$1,500.00	\$13,500		
Vanity Counters (Solid Surfacing)	33	LF	\$190.00	\$6,270		
C20 Stairs	-	NONE			\$0	\$0.00
C30 Interior Finishes	19,500	SF			\$508,184	\$26.06
Flooring (Carpet Tile Typical)	17,154	SF	\$7.76	\$133,147		
Tile (Ceramic)	2,346	SF	\$22.58	\$52,979		
Wall Finishes (Paint)	53,328	SF	\$4.39	\$233,849		
Ceilings (Paint, Stain, ACT)	12,645	SF	\$6.00	\$75,870		
Ceilings (Exposed Structure)	6,855	SF	\$1.80	\$12,339		

Item	Qty	Unit	Unit Cost	Line Cost	Total Cost	Unit Cost
Detail (Level 3)						
D SERVICES	19,500	GSF			\$2,026,715	\$103.93
D10 Conveying	-	NONE			\$0	\$0.00
D20 Plumbing	36	FIX			\$213,597	\$5,933.25
Fixtures	36	FIX	\$891.00	\$32,076		
Plumbing Roughin	36	FIX	\$4,636.00	\$166,896		
Plumbing Equipment	19,500	SF	\$0.75	\$14,625		
D30 HVAC	19,500	SF			\$897,605	\$46.03
Ventilation						
Air Handling W/ Heat Recovery	16,580	CFM	\$11.50	\$190,670		
Air Distribution System	12,645	SF	\$17.00	\$214,965		
Air Distribution System, Fire Bay	6,855	SF	\$6.00	\$41,130		
Heat Generation (Oil & Pellet Boilers)	1,170	MBH	\$42.00	\$49,140		
Heat Distribution	19,500	SF	\$12.50	\$243,750		
Controls	19,500	SF	\$7.00	\$136,500		
Test & Balance	19,500	SF	\$1.10	\$21,450		
D40 Fire Protection	19,500	GSF			\$117,000	\$6.00
Wet Pipe Sprinkler System	19,500	SF	\$6.00	\$117,000		

Item	Qty	Unit	Unit Cost	Line Cost	Total Cost	Unit Cost
Detail (Level 3)						
D SERVICES CONTINUED						
D50 Electrical	19,500	SF			\$798,513	\$40.95
Service & Distribution						
800A Service & Feeder	1	EA	\$48,000.00	\$48,000		
Panelboard & Feeders (200A)	4	EA	\$8,000.00	\$32,000		
Lighting						
General Lighting, LED	316	EA	\$750.00	\$237,094		
Fire Bay Lighting	20	EA	\$925.00	\$18,500		
Branch Wiring						
Convenience Outlets	342	EA	\$220.00	\$75,344		
Motor Circuits and Controls	19,500	SF	\$1.50	\$29,250		
Communications and Security						
Comm Equipment	1	LS	\$10,000.00	\$10,000		
Backbone and Cable Trays						
Comm - Outlets	70	EA	\$700.00	\$49,000		
Fire Detection & Alarm	19,500	SF	\$3.60	\$70,200		
Access Control	30	LOC	\$4,000.00	\$120,000		
Intrusion Detection	19,500	SF	\$0.50	\$9,750		
CCTV	10	EA	\$7,500.00	\$75,000		
Public Address	19,500	SF	\$1.25	\$24,375		

Item	Qty	Unit	Unit Cost	Line Cost	Total Cost	Unit Cost
Detail (Level 3)						
E EQUIPMENT & FURNISHINGS	19,500	GSF			\$140,275	\$7.19
E10 Equipment	19,500	SF			\$132,400	\$6.79
Prefabricated Cells	5	EA	\$25,000.00	\$125,000		
Refrigerator	2	EA	\$2,200.00	\$4,400		
Ranges	2	EA	\$1,500.00	\$3,000		
E20 Furnishings	19,500	SF			\$7,875	\$0.40
Training Room Seating, Office System Furniture Not Included, Assume FF&E Items						
Window Treatment	1,125	SF	\$7.00	\$7,875		
F SPECIAL CONSTRUCTION AND DEMOLITION	-	NONE			\$0	\$0.00
F10 Special Construction	-	NONE			\$0	\$0.00
F20 Selective Building Demolition	-	NONE			\$0	\$0.00
G SITEWORK	19,500	GSF			\$434,308	\$22.27
G10 Site Preparation	1	LS			\$155,759	\$155,759.26
Existing Site, No Clearing	-	NONE				
Earthwork						
Building	19,500	SF	\$2.00	\$39,000		
Parking and Drives	40,000	SF	\$2.88	\$115,370		
Sidewalks	1,500	SF	\$0.93	\$1,389		
G20 Site Improvements	19,500	SF			\$154,549	\$7.93
Roadways & Parking	4,444	SY	\$25.00	\$111,111		
Pedestrian Paving	1,500	SF	\$7.63	\$11,438		
Curbs	1,000	LF	\$32.00	\$32,000		
Landscaping	-	NONE				

Item	Qty	Unit	Unit Cost	Line Cost	Total Cost	Unit Cost
Detail (Level 3)						
G SITEWORK CONTINUED						
G30 Site Mechanical Utilities	200	LF			\$124,000	\$620.00
Water Service	100	LF	\$250.00	\$25,000		
Sewer Main	100	LF	\$190.00	\$19,000		
Fuel Storage	5,000	GAL	\$16.00	\$80,000		
G40 Site Electrical Utilities	-	NONE			\$0	\$0.00
Electrical To Building, By Utility, Not Included In The Estimate						
Communication To Building, By Utility, Not Included In The Estimate						
G90 Other Site Construction	-	NONE			\$0	\$0.00
Z MARKUPS	19,500	GSF			\$2,832,917	\$145.28
Z10 Contractor Markups					\$1,392,191	
Management & Site Facilities	12.0%			\$666,128		
OH&P	8.0%			\$497,376		
Mob/Demob	1.5%			\$100,719		
Room & Board (50% Of Labor)	1,706	MDAYS	\$75.00	\$127,969		
Z20 Contingency					\$1,440,726	
Estimating Contingency	15%			\$1,041,489		
Escalation (2014 Construction)	5%			\$399,237		
Total Estimated Cost	19,500	SF			\$8,383,984	\$429.95