

# HAINES BOROUGH PUBLIC NOTICE

## REQUEST FOR PROPOSALS PORCUPINE ROAD GRADING



The Haines Borough is requesting proposals from licensed, insured contractors for the grading of Porcupine Road. The contractor will be responsible for grading and rolling the eight miles of road beginning where the chip-sealed road ends and ending at the bridge located at the Big Nugget Mine. Grading must be the full width of the road. Work shall be completed by August 31, 2014.

Proposals shall include a lump sum for grading and rolling. A separate price should be included on a Time/Labor basis for hauling and grading additional material that may be available for this project. All proposals must be submitted with copies of current Alaska and Haines Borough Business Licenses.

The Borough will supply approximately 150 cubic yards of road topping material to be used in this project. The contractor shall submit a schedule at least three business days prior to needing the fill, and designate a location for the fill to be placed. The location of this additional material shall be authorized by the Borough prior to commencing work.

Proposals must be received by the Clerk no later than 10:00 a.m., Local Time, ~~Monday, July 21, 2014~~ Wednesday, **July 23, 2014 (per Addendum #1)**. Proposals may be mailed, hand-delivered, emailed, or faxed to:

Haines Borough Clerk's Office  
103 Third Ave. / P.O. Box 1209  
Haines, Alaska 99827  
Phone: 907-766-2231 ext. 31 or 36  
Fax: 907-766-2716  
Email: jcozzi@haines.ak.us

**Site Inspection:** Proposers are required to visit the work site to evaluate this project and to see the conditions under which the work described in this RFP will be performed. Contact Carlos Jimenez, the Director of Public Facilities, at (907) 314-0648 or [cjimenez@haines.ak.us](mailto:cjimenez@haines.ak.us) for additional information.

**Scope of Work:** The road surface shall be worked so that ruts are cut out and ditches pulled. Compaction of fill is required to create oriented smooth subsurface/surface layers and graded as necessary to create a smooth, drivable surface.

Fill area is required to match the existing road prism and surface elevation.

Construction methods allowing ingress and egress of local traffic shall be required during the project term.

**Contractor Responsibilities:** Mobilization/Demobilization to the described area on Porcupine Road.

~~Removal of material from roadway, to 10 feet beyond shoulders of road.~~ **(per Addendum #1)**

Provide all construction materials, labor and equipment to complete the described work.

Demobilize and cleanup of the worksite. All areas will be left in as clean or better condition than when the contractor arrived.

The Borough reserves the right to reject any and all proposals, to waive any irregularities in the proposal process, or to negotiate with the low proposer.

If the Borough is satisfied with the deliverable at the end of the job, the Borough and the chosen contractor may negotiate this contract in one-year increments for up to four years.