ADDENDUM TO THE CONTRACT
for
HAINES BOROUGH LIBRARY BUILDING CONTROLS CONVERSION

ADDENDUM NO.: **ONE**

ISSUED BY: Murray & Associates, P.C.
PO Box 21081
Juneau, AK 99801
(907) 780-6151
for the Haines Borough

DATE ADDENDUM ISSUED: April 8, 2014

The following items of the contract are modified as herein indicated. All other items remain the same. This is an electronic addendum. A confirming copy will not be mailed to you.

This addendum includes 1 page. If not complete, please call 907-780-6151 and we will resend it.

Acknowledge receipt of this addendum on your bid form.

Item No. 1 **BID OPENING DATE: Change Bid Opening Date from April 10, 2014 to April 14, 2014, 2:00 p.m. Local.**

Item No. 2 Drawing Sheet M101 Construction Note 3: Delete and *Replace* with the following:
4: REUSE ALL RADIANT ZONE THERMOSTATS. FIELD VERIFY OPERATION OF ROOM THERMOSTATS DURING PRECONSTRUCTION VISIT TO SITE, PROVIDE FIELD REPORT OF DEFICIENCIES. RADIANT ZONE THERMOSTATS ARE TEKMAR 055, 24 VOLT. INCORPORATE THE EXISTING ROOM THERMOSTATS INTO THE DDC SYSTEM FOR CONTROL AND MONITORING. REUSE WIRING BETWEEN THERMOSTATS AND MECHANICAL ROOM.

Item No. 2 Drawing Sheet M101 Construction Note 4: Delete and *Replace* with the following:
4: REUSE ALL RADIANT ZONE AUTOMATIC VALVE ACTUATORS. FIELD VERIFY OPERATION OF ROOM THERMOSTATS DURING PRECONSTRUCTION VISIT TO SITE, PROVIDE FIELD REPORT OF DEFICIENCIES. EXISTING ZONE VALVE ACTUATORS ARE UPONOR/WIRSBO A3020522, 24 VOLT. INCORPORATE THE EXISTING ACTUATORS INTO THE DDC SYSTEM FOR CONTROL AND MONITORING. REUSE WIRING BETWEEN ACTUATORS AND MECHANICAL ROOM.

Item No. 3 Drawing Sheet M102 Construction Note 2, Add to end of note: REUSE RADIANT ZONE VALVE ACTUATORS, TOTAL OF 26 ACTUATORS FROM THE THREE MANIFOLDS. REUSE WIRING BETWEEN ACTUATORS AND MECHANICAL ROOM.

Item No. 4 Drawing Sheet M103, Control Schematic For Boiler And Radiant Pumps: Delete DO point on the existing burner contactor.

Item # 5 Spec Section 230926, Acceptable Manufacturers, 1.6. Add Line F. as follows:
F. Meridian Systems, Inc.

Item # 6 Spec Section 230926 Building Automation And Automatic Controls, Paragraph 3.3.C. Test and Balance: Delete paragraph C. There is not anticipated to be any Testing and Balancing Work or a TAB subcontractor on this project.

End of Addendum